# DETAIL SECTION A

Scale 1:20

KID'S POOL

granite pool finishes.
pool walls (vertical surfaces) = black flamed 300x600mm panels butt-jointed

pool floor (horizontal surfaces) = pale grey 100x600mm strips butt-jointed
stone colour/finishes to LA's selection

REFER TO LP-LD-POOL-05
overflow channel for kid's pool, location and opening size for overflow opening to specialist detail.

300x600mm perimeter pool trim in 20mm thk granite finish w/ 10mm chamfered 50x50mm head. stone to LA's selection

100x600mm, 20mm thk granite pavers w/ laid 5mm shadow gaps along horizontal lines, and butt-jointed along vertical lines

ground level (+3.60) is gently ramped up to meet platform level of +3.80

FFL+3.95
WL+3.85
TOW+3.83
FFL+3.55
FFL+3.25
EL+3.60
1245
200
350
300
600
100
70
50
20

100W pool lights by specialist to LA's approval

to balancing tank/ pump

screed to fall

RC structure + waterproofing to engineer's detail

ADULT'S POOL

5x3mm deep groove along length of tension edge panel

screed to fall min. 1:50

FFL+3.80
TOW+3.90
WL+3.90
TOW+3.60
100
60
30

ADULT'S POOL

granite pool finishes.
pool walls (vertical surfaces) = black flamed 300x600mm panels butt-jointed

pool floor (horizontal surfaces) = pale grey 100x600mm strips butt jointed
stone colour/finishes to LA's selection

100mm deep loose laid ¾" - 1" gravel chippings on galvanised grating to contractor's proposal

75x75mm, 6mm thk MS L-angle trim painted black (Nippon Cupon Aerocoat)bolted to overflow upstand

6m wide platform with random tree planting
trees to be planted first prior to slab casting to accomodate massive rootball size

walkway to breakfast area

FFL+3.80
TOW+3.90
TOW+3.60
WL+3.90
FFL+3.95
100
300
700
1200
100
50

300W pool lights by specialist to LA's approval

to balancing tank/ pump

FFL+2.70